

DETECTION OF LOW MASS-RATIO STELLAR BINARY SYSTEMS

KEVIN GULLIKSON¹, SARAH DODSON-ROBINSON¹

Accepted to the Astrophysical Journal on October 19, 2012

ABSTRACT

O- and B-type stars are often found in binary systems, but the low binary mass-ratio regime is relatively unexplored due to observational difficulties. Binary systems with low mass-ratios may have formed through fragmentation of the circumstellar disk rather than molecular cloud core fragmentation. We describe a new technique sensitive to G- and K-type companions to early B stars, a mass-ratio of roughly 0.1, using high-resolution, high signal-to-noise spectra. We apply this technique to a sample of archived VLT/CRIRES observations of nearby B-stars in the CO bandhead near 2300 nm. While there are no unambiguous binary detections in our sample, we identify HIP 92855 and HIP 26713 as binary candidates warranting follow-up observations. We use our non-detections to determine upper limits to the frequency of FGK stars orbiting early B-type primaries.

Subject headings: binaries: spectroscopic — stars: early-type — stars: formation

1. INTRODUCTION

O- and B-type stars are often found in binary or multiple systems: Mason et al. (2009) estimate that at least 57% of O-stars are in spectroscopic multiple systems, and at least 75% are in any type of binary or multiple system. Yet the multiplicity fraction of high-mass stars may be underestimated due to the difficulty of detecting low-mass secondary stars (Sana & Evans 2011). While the mass-ratio distribution is reasonably well known for high-mass binaries with mass-ratio $q \equiv M_s/M_p > 0.2$, there are almost no constraints for low mass-ratio binaries. However, binaries of low mass-ratio are important probes of star formation since they may have formed in a different way than approximately equal-mass binaries. Here we define low mass-ratios to be those with $q < 0.2$, where M_s is the mass of the secondary (lower mass binary component), and M_p is the mass of the primary (higher mass binary component). We also use the term “low-mass” to describe star with $M \lesssim 1M_\odot$, and “high-mass” to describe stars with $M \gtrsim 5M_\odot$.

1.1. Binary Formation in High-Mass Stars

With such a high fraction of high-mass stars found in binary or multiple systems, any theory of high-mass star formation should be able to explain the high binary formation rate. There are several mechanisms by which binary stars may form: fission (Lyttleton 1953; Lebovitz 1974, 1984), in which a molecular core begins spinning fast enough as it collapses that it splits into two stars; core fragmentation (see e.g. Boss & Bodenheimer 1979; Boss 1986; Bate et al. 1995), in which a collapsing core develops two or more overdensities which then begin collapsing separately; and disk fragmentation (see e.g. Kratter & Matzner 2006; Stamatellos & Whitworth 2011), in which the circumstellar disk surrounding the primary star becomes gravitationally unstable and creates a secondary star. While the fission scenario was once thought to be important, it has since fallen out of favor because the viscous dissipation timescale, which

would drive a spinning body towards fission, is much longer than the core collapse timescale (Tohline 2002) and because hydrodynamic simulations fail to cause the rotating core to actually split rather than just deform (Tohline & Durisen 2001). Both core and disk fragmentation are still thought to be viable binary formation mechanisms. It is likely that both mechanisms play a role in shaping the binary mass-ratio and separation distributions. In the formation of higher-order multiples, it is even possible that both mechanisms operate in the same system.

The primary method of forming binary systems is thought to be core fragmentation. As a molecular cloud begins isothermally collapsing, its density increases, causing the Jeans mass to decrease. Thus, an initially Jeans-mass collapsing core can fragment into smaller objects. Core fragmentation will initially yield binaries with separations $10AU < a < 1000AU$, which may move closer by interacting with the surrounding gas, a circumbinary disk, or through dynamical interactions with other nearby stars (Bate et al. 2002). For $\sim 1M_\odot$ primary stars, the observed mass-ratio distribution is well fit by assuming both components of the binary are chosen randomly from the stellar initial mass function, and later evolve through accretion and dynamical interactions (Kroupa et al. 2003). Assuming independent component masses chosen from the IMF, a binary with a $10M_\odot$ primary would most often have a $0.1M_\odot$ secondary, giving an initial mass ratio near $q = 0.01$. The unmodified mass-ratio distribution of high-mass binaries would therefore strongly favor low mass ratios. However, accretion of high specific angular-momentum gas from either the collapsing molecular core or the circumbinary disk will preferentially be captured by the lower-mass companion, driving the binary mass-ratio toward unity and decreasing the orbital separation (Bate 2000; Bonnell & Bate 2005). Additionally, dynamical interactions tend to replace low-mass binary companions with higher-mass ones, or to kick the lower-mass component out to a wide orbit and create a hierarchical triple system. Over time, these processes tend to create high-mass binary systems with nearly equal masses and small sep-

¹ Astronomy Department, University of Texas, 1 University Station C1400, Austin, TX 78712, USA.
 kgulliks@astro.as.utexas.edu

arations (Bate et al. 2002). Dynamical interactions are most important in dense environments where the probability of stellar encounters is high. Therefore, they are probably more important in dense OB star clusters than in the much looser OB associations, where many B stars are found.

Another potentially important way to form binary systems is disk instability (see e.g. Kratter & Matzner 2006; Stamatellos & Whitworth 2011). In this scenario, the fragment forms in an unstable circumstellar disk with an initial separation of $\sim 100 AU$ and initial mass-ratios near $q \sim 0.03$, similar to the core fragmentation case (Kratter & Matzner 2006). The final mass-ratio is expected to rise, but not as significantly as in the core fragmentation scenario in which the fragment can form sooner. Typical mass-ratios near $q \sim 0.1$ are expected, though the picture is far from complete. A semi-analytical treatment of embedded protostellar disks by Kratter et al. (2008) finds that massive stars with $M > 2M_{\odot}$ maintain $0.01 - 0.1M_{\odot}$ in orbiting fragments after about 2 Myr. Krumholz et al. (2007) simulate a $100M_{\odot}$ collapsing core for a much shorter time (20 kyr), but also find that the disk fragments and that the final fragment mass ratio is $q \approx 0.1$. However, Krumholz et al. (2009) simulate the same mass core but start it with a slow solid body rotation instead of a turbulent velocity field and run the model for about twice as long (57 kyr), and find that it leads to a very massive binary ($M_1 + M_2 = 70M_{\odot}$) with a mass-ratio $q = 0.7$. Work by Clarke (2009) indicates that as mass is transported inwards onto the star, the outer disk can become unstable at late times. This instability can lead to a delayed disk fragmentation, with a fragment mass-ratio in the range $0.1 < q < 0.5$. The simulations by Clarke (2009) were done for a $\sim 1M_{\odot}$ primary star, and the delayed fragmentation occurred after about 10^5 years. Delayed fragmentation may not be possible in disks surrounding high-mass stars, as the time at which fragmentation occurs is comparable to the disk dispersal timescale (Klahr & Brandner 2006). However, if it does occur, the similar fragmentation and dispersal timescales suggest that the fragment would not undergo significant accretion or migration and would leave a wide binary ($a \approx 100 AU$) with mass-ratio in the range $0.1 < q < 0.5$.

Unfortunately, there are no true binary population synthesis simulations for high-mass binary systems formed by either mechanism discussed above. The lack of population synthesis models is driven by computational issues; a collapsing cloud that reproduces the stellar mass function and generates enough high-mass stars to meaningfully analyze the binary statistics would have to be very massive and therefore difficult to simulate. Disk fragmentation simulations often either stop the simulation once a fragment forms rather than follow its mass accretion history (e.g. Boss 2011; Krumholz et al. 2007), or lack high enough resolution to follow the secondary very near the star (e.g. Bonnell & Bate 2005). Fortunately, such models may be in the near future. Realistic simulations of massive collapsing molecular clouds have begun appearing that can meaningfully discuss the multiplicity of low-mass binary systems (Bate 2012; Krumholz et al. 2012). These simulations reproduce the observed increase in multiplicity fraction with primary star mass,

but do not yet generate enough high-mass binary system to compare the parameter distributions to observations. Despite the current lack of models, we can draw the general conclusion that disk fragmentation tends to produce lower-mass companions than core fragmentation. For this reason, probing the low mass-ratio regime can provide information on the relative importance of both scenarios in forming high-mass binary systems, and may help constrain models once computational power increases.

In addition to binary star formation, disk instability is often invoked as a way to form planets of a few Jupiter masses orbiting $\sim 1M_{\odot}$ stars. While the massive star formation process as a whole may not simply be a scaled up version of low-mass star formation (Zinnecker & Yorke 2007), the process of disk fragmentation may be. One expects that disks around high-mass stars, with correspondingly higher accretion rates and more mass, fragment more often than disks around low-mass stars (Boss 2011, 2006; Dodson-Robinson et al. 2009; Kratter & Matzner 2006). Thus, if disk fragmentation plays an important role in high-mass star formation, it may also play a role in low-mass star formation by creating $\sim 10M_{Jup}$ planets and substellar companions.

1.2. Observing low mass-ratio binaries

Detection of OB-star binaries with mass-ratio $q \approx 0.1$ or lower is very difficult, since the ratio of the secondary flux F_s to the primary flux F_p is $F_s/F_p \sim 10^{-3}$ or lower in the V-band. Imaging surveys can detect such contrast ratios for wide orbits, but lose sensitivity as the separation decreases below about $1''$ (e.g. Maíz Apellániz 2010). Spectroscopic binary surveys do well for short-period systems where a full orbit can be mapped in a reasonable amount of time, but lose sensitivity for periods greater than about one year (e.g. Sana et al. 2009; Evans et al. 2010). However, low-mass companions ($q \lesssim 0.2$), which induce a small reflex motion on the primary, are very difficult to find with traditional spectroscopic surveys.

One method to find low-mass companions to late B-type primaries is to search for high x-ray emission. Stars later than about B3 are not expected to have strong enough winds to emit X-rays (Gagné et al. 1997), and stars of earlier type than about A7 do not have a radiative-convective boundary that can drive a magnetic dynamo and create an X-ray generating corona (Schmitt 1997). Stars in between spectral types B4 and A7 with strong X-ray emission are thought to have young low-mass companions, because the luminosity and X-ray spectral energy distribution is similar to observed T-Tauri stars (Huélamo et al. 2000). Evans et al. (2011) use this fact to search for low-mass companions to late B-stars in the open cluster Trumpler 16. They find a significant number of companions, and set the multiplicity fraction at 39%. This value is a lower limit, but the authors believe that the true value is not much above 39%. Unfortunately, X-ray imaging is not effective for primary star spectral types earlier than B3, which are also strong x-ray emitters (Gagné et al. 1997) and will drown out any companions.

In this paper, we introduce a technique that is sensitive to young binary systems with secondary temperatures $4000 \text{ K} \lesssim T_{\text{eff}} \lesssim 6000 \text{ K}$. For early B-type primaries with ages ~ 15 Myr, these temperatures correspond to




FIG. 1.— This figure illustrates the approximate flux ratio limit to the detection method outlined in section 2. *Top panel:* Residuals after telluric correction (see section 4) for chip 2 of HIP 80582 are in black, with an atmosphere model for an $0.9M_{\odot}$ star at 50.1 Myr below it in red. The flux ratio at this age is $F_s/F_p = 0.0092$. *Middle panel:* The scaled model spectrum was added to the telluric residuals, and then the sum was cross-correlated with the model. Despite the signal being significantly below the noise level, the star was detected at a high significance. The y axis, in units of the standard deviation of the cross-correlation function, shows that the significance of the peak is over 4σ . *Bottom panel:* Same as the middle panel, but the model spectrum was added to the residuals with a 50 km s^{-1} velocity offset.

mass-ratios $q \approx 0.05 - 0.3$, right where we expect to see binaries formed by disk instability (see section 1.1). Rather than attempting to detect the reflex motion of the parent star as in exoplanet searches and SB1 binaries, we attempt to directly detect the spectrum of the young low-mass companion using high signal-to-noise, high-resolution data. There is a multitude of archived B-star observations in the near-infrared, where they are used as telluric standard stars to remove the absorption spectrum of the Earth’s atmosphere (telluric lines). This method is equally sensitive to all separations within the point spread function, which is dominated by the seeing since the adaptive optics are not used in telluric standard star observations. A typical seeing of $\sim 0.8''$ corresponds to up to $\sim 900 \text{ AU}$ for targets within a few kpc. In this paper, we describe a search for young F5-K9 type companions in archived VLT/CRILES spectra of 34 early B-type stars.

In section 2 we describe our detection method in more detail. Section 3 describes the B-star sample we use in this work. Section 4 contains the data reduction and telluric correction methods. We summarize our results in section 5. We examine the completeness of our sample in section 6 and put limits on the multiplicity fraction as a function of mass-ratio in section 7. Finally, we present our conclusions about the prevalence of low mass-ratio companions to early B-type stars and discuss how our results constrain star formation mechanisms in Section 8.

2. DIRECT SPECTRAL DETECTION METHOD

We describe here our method to detect the emission from an approximately solar-mass star orbiting an early B-type star, which we will hereafter call the direct spectral detection method. The basis of this method is to cross-correlate a high signal-to-noise ratio B-star spectrum with a synthetic F, G, or K star spectrum. If a

low-mass star with such a spectrum is orbiting the B-star, we expect to find a peak in the cross-correlation function at the radial velocity corresponding to the low-mass star’s motion. A peak in the cross-correlation function should appear even if the flux from the low-mass star is comparable to or even slightly less than the noise level in the spectrum. Figure 1 illustrates the approximately limiting case for the flux ratio. The top panel shows a fully reduced CRILES spectrum of HIP 108975 (see section 4) with a model spectrum for an $0.9M_{\odot}$ star at a realistic flux ratio below it. We used evolutionary tracks published by Landin et al. (2008) to evolve the secondary star to 50.1 Myr, the age of the system (Tetzlaff et al. 2010), in order to determine the flux ratio between the primary and secondary. The secondary star model was then added to the telluric-corrected B-star spectrum at two different velocities. It is clear that the model spectrum has an amplitude much smaller than the noise. Nonetheless, the bottom two panels show that a cross-correlation will have a peak with high significance at the velocity of the secondary star.

A careful choice of the wavelength region is critical for the direct spectral detection method. First, we want a wavelength region where the B-star spectrum is mostly continuum (i.e. very few spectral lines). Since B-stars have few spectral lines, it is easy to find a such a spectral region. Secondly, we want a region where the low-mass star would have many closely spaced, strong lines. The more lines there are in the low-mass star, the stronger the peak will be in the cross-correlation function. Finally, we want a spectral region where the flux ratio between the low-mass and the high-mass star is maximized. It is not helpful to go much redder than a few microns for companions with $T > 4000\text{K}$, because both the high-mass and the low-mass star are firmly in the Rayleigh-Jeans limit by this point, where the flux ratio is approximately constant. For this project, we choose wavelengths from




FIG. 2.— *Top panel:* The telluric spectrum (absorption due to Earth’s atmosphere) in the wavelength range from 2290 – 2400 nm. Most of the lines are from CH_4 , with a few H_2O lines appearing in the right half. *Bottom panel:* The model spectrum of a 5500 K star with $\log(g) = 4.0$ and solar metallicity. Note that the line density of telluric lines is comparable to or greater than that of the star model, and many of the telluric lines are stronger than the stellar lines.

2300 – 2400 nm, which is the CO $\Delta\nu = 0 - 2$ bandhead in the low-mass star.

There is both a lower and upper mass detection limit. Secondary stars that are too cool will be too faint, and any signal will be lost in the noise. Additionally, a more massive (and hotter) primary star will decrease the flux ratio, and push the lower mass limit up. On the other end, secondary stars that are too hot will dissociate CO, destroying the bandhead that we are looking for. The temperature and size of the secondary star will depend on its age as well as its mass since it will still be evolving towards the Main Sequence during the lifetime of the B-star. The exact mass sensitivity will thus depend on the age, primary star mass, and signal-to-noise ratio of the system being observed.

The detector resolution is also important for the direct spectral detection method. Deeper lines, providing more contrast from the continuum, are easier to detect than broad, shallow lines. In addition, narrow spectral lines will result in a stronger, narrower peak in the cross-correlation function, which is most sensitive to the steep line edges. Therefore, we want the spectral lines in the low-mass companion to be as deep and narrow as possible. The intrinsic width of CO bandhead lines is roughly $5\text{--}7 \text{ km s}^{-1}$. In order for the observed line width to be this small, we need the resolution of the instrument to be $R = \lambda/\Delta\lambda \gtrsim 50000$.

There are two main difficulties with the direct spectral detection method: telluric line removal and the low flux ratio between the primary and secondary star. Figure 2 shows the transmittance through the Earth’s atmosphere (the telluric spectrum) in the wavelength range we are interested in. Most of the spectral lines are from methane, with a few deep water lines towards the red end of the range shown (See section 4 for details on the tel-

luric line removal). The low flux ratio makes the telluric contamination especially troublesome, since the telluric lines are stronger than the lines in the companion star spectrum. The flux ratio of $F_s/F_p \sim 10^{-2}$ effectively sets a lower limit on the signal-to-noise ratio for which the direct spectral detection method is possible. Any flux coming from a low-mass star will be completely buried in the Poisson noise for spectra with $\text{SNR} \ll 100$. Removal of the telluric contamination will add more noise to the spectrum, so a spectrum should have SNR of a few hundred *before telluric line removal* to have a good chance of detecting a companion.

3. STAR SAMPLE

B-type stars are commonly used in the near-IR as telluric standard stars. Astronomers will observe their science targets, and then move to a B-type star. Since B-type stars have few spectral lines relative to cooler stars, most of the observed spectral lines will be from the absorption of Earth’s atmosphere (telluric absorption). Therefore, these stars provide an empirical estimate of the telluric spectrum; division of the science spectrum by the normalized standard star spectrum will mostly remove the telluric lines.

Since B-type stars are commonly used as above, there are many high signal-to-noise ratio ($S/N \gtrsim 100$) observations of such stars in archived data. We used the VLT/CRIRES archive in this project. CRIRES is a high resolution ($R = \lambda/\Delta\lambda \approx 100000$) infrared spectrograph on the VLT at Paranal Observatory. The detector consists of four 1024×512 ccd chips that are mosaiced end-to-end, and the spectrum falls across them. There are several wavelength settings available, which determine what parts of the spectrum fall on each chip. For wavelength settings in the CO bandhead near 2300 nm, each

chip will hold roughly 10 nm of spectrum with roughly 1-2 nm gaps between the chips.

To generate the sample, we started with all single, main sequence B0-B5 stars with CRIRES observations from 2300-2400 nm. We then excluded any shell stars, which have circumstellar disks (Porter & Rivinius 2003) that may create false positives. Table 1 shows the complete sample used in this project. The spectral types and ages were obtained from a catalog of nearby young stars (Tetzlaff et al. 2010). The one exception is HIP 97611, which was not in Tetzlaff et al. (2010). For this star, the age was taken from Westin (1985) and the spectral type from the Simbad database². The distances to all stars were determined from parallaxes given in the Simbad database. The maximum separation column estimates the approximate maximum separation of the binary orbit we are sensitive to, assuming a seeing of 0.8" which is typical of Paranal Observatory. The median of the maximum separations to which we are sensitive is 124 AU. The final column gives the number of distinct observations of the star. We count all nodding positions taken on a given night with the same detector wavelength setting as one observation.

4. DATA REDUCTION AND TELLURIC CORRECTION

The data reduction was done using standard methods in IRAF³. All observations were taken in an AB or ABBA nodding pattern. For each set of AB nods, A-B and B-A frames were made to remove any atmospheric emission lines and dark current. The resulting difference images were then treated to a quadratic nonlinearity correction, using coefficients made available by the CRIRES team. The corrected frames were then divided by a normalized flat-field. Due to the slit curvature, the spectrum can shift by up to a pixel in the dispersion direction between the A and B nod positions. Therefore, combining the 2D frames before extraction can reduce the spectral resolution and affect the line shapes. For this reason, we combined the nodding positions only after the wavelength calibration and telluric correction. Each nod position was extracted using the optimal algorithm in the `apall` task in IRAF. The spectra were wavelength calibrated using a model telluric spectrum generated with the atmospheric modeling code LBLRTM (Clough et al. 2005).

For telluric correction, we used a similar procedure to the one outlined by Seifahrt et al. (2010). The atmosphere modeling code LBLRTM was used to generate a synthetic telluric absorption spectrum. The abundances of water, methane, and carbon monoxide were fit using a Python implementation of a Levenberg-Marquardt non-linear least squares fitting algorithm. The Levenberg-Marquardt fit also refined the wavelength solution to the telluric model, fit the continuum, and fit the resolution of the spectrograph with a Gaussian profile. The FWHM of the profile was the only free parameter in the resolution fit.

The LBLRTM code expects a model atmosphere, which contains the temperature, pressure, and abun-

dance of 30 molecules as a function of atmospheric height. For the majority of molecular species, we used a mid-latitude nighttime MIPAS⁴ profile, which provides the temperature, pressure, and abundances of various molecules in 1 km intervals from sea level to 120 km. The low-altitude ($z \lesssim 30$ km) temperature, pressure (Kerber et al. 2010), and humidity (Chacón et al. 2010) profiles were obtained from radiosonde data taken from Paranal Observatory.

The LBLRTM atmospheric modeling code comes with a molecular line list based on the HITRAN 2008 database (Rothman et al. 2009), with a few molecules individually updated. Since none of these updates were relevant for the wavelength range from 2300–2400 nm, we in essence used the stock HITRAN 2008 database. However, in the process of modeling, we found several water and methane lines that were consistently under- or over-fit. For these cases, we manually adjusted the line strengths in the database. The line strengths were fit visually and should not be considered rigorous new line strengths. Table 2 summarizes these changes.

In some of the 2007 data, the first chip was not well illuminated by the flatfield lamp. This introduced an unphysical continuum shape in the data and made the resulting model fit very poor. For these cases, we ignored the first chip in further analysis. In addition, the fourth chip has several bad pixels on the left edge and a streak down the middle. None of the telluric model fits were very good on this chip, and so we have ignored it completely in our analysis.

After the observed spectrum was fit, we found that the residuals still contained large spikes, even on the good detector chips. These spikes can come from a variety of sources. For the deepest lines, simple Poisson noise can create large residuals when dividing by the telluric model. In addition, a poorly fit continuum may cause the model to over- or under-estimate the abundance of a given molecule. This can be especially troublesome for water lines, for which only a few exist in the wavelength region we are investigating. If a strong water line is near the edge of the chip, where the continuum is usually least certain, the best-fit water abundance may be skewed and cause none of the water lines to be well fit. We do know that large residuals are *not* coming from the spectrum of a low-mass star, due to the expected flux ratio between the primary and secondary, $F_s/F_p \sim 10^{-2}$. Any residuals with amplitude greater than 1% of the continuum level come from uncorrected telluric lines, cosmic rays, or bad pixels.

In order to minimize these spikes, we performed a second fit to any residuals significantly above the continuum noise level. To make sure we were not fitting away any low-mass star lines, we only corrected spikes whose amplitude was greater than 5% of the continuum level. In this second fit, we first attempted to fit a Gaussian to each spike. If the spike was well fit by a Gaussian, we divided the residuals by the fit. If not, we simply masked out the line core, so that it would not affect the cross-correlation in later analysis (see section 2). Figure 3 shows the steps involved in the telluric correction. Notice that the secondary correction removes the large residuals, while leaving the rest of the spectrum unaf-

² <http://simbad.u-strasbg.fr/simbad/>

³ IRAF is distributed by the National Optical Astronomy Observatories, which are operated by the Association of Universities for Research in Astronomy, Inc., under cooperative agreement with the National Science Foundation.

⁴ <http://www-atm.physics.ox.ac.uk/RFM/atm/>




FIG. 3.— The telluric correction steps for chip three of CRIRES wavelength setting $\lambda_{ref} = 2329.3$ nm. *Top panel:* Normalized spectrum (black), with the best-fit telluric model (red). *Middle panel:* Residuals after dividing the observed spectrum by the telluric model. Note the large spikes near 2328.5, 2331, and 2335 nm. *Bottom panel:* Correction after fitting the large residuals to Gaussians.

fected.

The telluric correction described above usually reduced any telluric lines to near the Poisson noise level in the spectrum, which is the best a fitting routine can do. To search for any systematic errors in the telluric correction, we added all spectra of each wavelength setting together to make a series of master telluric residual spectra. These master spectra had less random noise than any individual observation, and therefore we were immediately able to see whether some telluric lines are systematically under- or over-fit. We found that for wavelength settings with at least ten spectra in our sample, dividing the corrected spectra by this systematic telluric residual template increased the sensitivity to companions. We did not make this final correction for wavelength settings with fewer than ten individual spectra in our sample.

5. RESULTS

Each telluric residual spectrum was cross-correlated against a suite of model atmospheres generated by the Phoenix stellar atmosphere code (Hauschildt et al. 1999). All model spectra had solar metallicity. The effective temperatures ranged from 3000–7200 K, in 100K intervals. We used several surface gravities based on the stellar temperature. For the model secondary stars with $3000 < T_{eff} < 3600$, which would have to be very young (and large) to be detectable, we used a $\log(g) = 3.5$. For the secondaries with $3600 < T_{eff} < 6500$, we used $\log(g) = 4.0$. Finally, we used $\log(g) = 4.5$ for $T_{eff} > 6500$, which can be detected closer to the Main Sequence. We found that the surface gravity has only a very small effect on the cross-correlation, which is more sensitive to the line position than its precise width or depth. We compiled a list of all cross-correlations that show a single peak with at least 3σ significance. For a given telluric-corrected residual spectrum, several model atmospheres may generate a significant peak at the same velocity. This is because the model spectra of two stars differing by only a few hundred kelvin are not very different. To keep from counting peaks twice, we only counted the cross-correlation that resulted in the most significant peak at a given velocity. We then attempted to reject spurious peaks caused by the noise or incomplete telluric

line removal in a multi-stage process.

The first rejection stage was done by identifying peaks in the cross-correlation caused by telluric residuals. To do this, we cross-correlated a spectrum uncorrected for telluric absorption with the same suite of model atmospheres as we used for the corrected spectra (see above). We did these cross-correlations for one observation of each wavelength setting. The cross-correlation of uncorrected spectra with model-atmosphere spectra generated a series of cross-correlations with peaks arising exclusively from telluric lines. We visually compared all of the binary candidate signals with these telluric cross-correlations. If the dominant cross-correlation peak was at the same velocity and had a similar width as a peak in the telluric cross-correlation function corresponding to the same wavelength setting and secondary model temperature, we assumed that the peak was caused by incomplete telluric removal and rejected the candidate. There were several cross-correlations with peaks at the same location as a telluric peak, but with a different width. In these cases, we marked the candidate as probably coming from incomplete telluric correction, but did not reject the candidate.

Next, we determined whether the signal-to-noise ratio and telluric line removal in a given observation would allow us to detect the candidate companion star. To do this, we added a model atmosphere with the same temperature as the candidate to the telluric-corrected spectrum at 17 different radial velocities ranging from -400 to 400 km s^{-1} . We do not expect to see any peaks from real companions with $|v| > 400 \text{ km s}^{-1}$, the approximate radial velocity of a $1M_{\odot}$ star orbiting a $10M_{\odot}$ star such that the stellar surfaces are in contact. The flux ratio of the model atmosphere to the primary was obtained by interpolating pre-main-sequence evolutionary tracks from Landin et al. (2008) at the age of the system, as well at $\text{age} \pm \sigma_{age}$. The primary star ages for our sample are given in Table 1. We cross-correlated each of these semi-synthetic spectra against the model spectrum; if the largest peak was at the correct velocity, we counted the star as detected. If the star was not detected in the sensitivity analysis at least 50% of the time, we rejected the candidate. The significance of the correct peak in the




FIG. 4.— Cross-correlation for HIP 26713, using a 5600 K star model spectrum as template. The y-axis is in units of the standard deviation of the cross-correlation function. The peak is very near the maximum velocity of $|v_{\max}| = 256 \text{ km s}^{-1}$, assuming a circular orbit (see equation 1). The likelihood of observing the system nearly edge on and at a quadrature point, so that $|v| \sim |v_{\max}|$, is $p \approx 0.01$. However, it is possible that the system has an eccentric orbit, effectively increasing $|v_{\max}|$.

cross-correlation function can vary greatly, depending on where the stellar spectrum falls in relation to the telluric line residuals. Therefore, we cannot usually reject a peak based solely on its significance.

We then visually inspected the remaining candidate cross-correlations, picking out those with a single dominant peak with $|v_r| < v_{\max}$ where v_{\max} is the maximum possible radial velocity for a star of temperature T_{sec} to be orbiting a hotter star of temperature T_{prim} with a semimajor axis a . Assuming a circular orbit, v_{\max} is given by

$$v_{\max} = \sqrt{\frac{2G(M_{\text{prim}} + M_{\text{sec}})}{R_{\text{prim}}}} \cdot \frac{T_{\text{sec}}}{T_{\text{prim}}} \quad (1)$$

where M_{prim} and M_{sec} are the masses of the primary and secondary stars, respectively, and R_{prim} is the radius of the primary star. The primary masses are given in Tetzlaff et al. (2010), while the radii and primary star temperatures were estimated from spectral type relations given in Carroll & Ostlie (2006). An eccentric orbit could have a larger maximum velocity than that estimated by equation 1, if the orbit was oriented such that the the secondary star was moving directly towards or away from earth at or near periastron. A star in an eccentric orbit cannot get so close to the primary that they touch, and its *average* distance must still be far enough to allow for the observed secondary star temperature. These conditions lead to a maximum eccentricity, given by

$$e_{\max} = 1 - \frac{v_{\max}^2(R_{\text{prim}} + R_{\text{sec}})}{G(M_{\text{prim}} + M_{\text{sec}})} \quad (2)$$

where R_{prim} and R_{sec} are the radii of the primary and secondary stars, respectively, and v_{\max} is the maximum circular velocity given by equation 1. Typical values give $e_{\max} \approx 0.6$. Eccentricities near this value could allow for velocities significantly greater than v_{\max} given by equation 1.

The above analysis is summarized in Table 3. There are two binary candidate systems that we have not been

able to reject. For both of these, we checked what other observations the candidate star had within the CO band-head spectral region (2300 – 2400 nm). The analysis of each of these stars is done separately below.

5.1. HIP 26713

The cross-correlation for this candidate is shown in figure 4. The strong peak at -220 km s^{-1} has a significance just over 4σ , and corresponds to a 5600 K star model. A sensitivity analysis (Table 3, step 2) gives a median peak significance of $\sim 6\sigma$ with a large ($\sim 2\sigma$) spread. Due to the large spread, we cannot reject the peak based on the observed significance.

The candidate radial velocity amplitude of 220 km s^{-1} is very near the upper limit given by equation 1 of 256 km s^{-1} . If this candidate is a real binary companion, it must have been observed very near its radial velocity maximum and the orbital inclination must be very near edge-on. Assuming a circular orbit and equal probabilities of observing any given phase or inclination, the probability of this occurring for this system is ~ 0.01 . However, the probability for one system in our entire sample to be caught with this chance alignment rises to 0.14. In addition, we cannot discount the possibility of an eccentric orbit leading to a higher value of v_{\max} than estimated by equation 1. Without more data, we can neither confirm nor disprove the existence of a companion star orbiting HIP 26713.

If HIP 26713 is a true binary system, evolutionary tracks by Landin et al. (2008) give a secondary star mass of $1.6 \pm 0.2 M_{\odot}$. The mass of the primary star is $9.4 \pm 0.2 M_{\odot}$ (Tetzlaff et al. 2010), giving a mass-ratio of $q = 0.17 \pm 0.02$. For a circular orbit, the corresponds to an orbital period of 10.0 days. If the companion star is on an eccentric orbit, its true period would be longer than this.

5.2. HIP 92855

There were seven observations of HIP 92855 on different dates, all with the 2336 nm wavelength setting. The cross-correlations for four of the observation dates show a single strong peak when using a 6100K model




FIG. 5.— Cross-correlations for HIP 92855, for all dates observed. A 6100 K star model spectrum is used as the template for each cross-correlation. The y-axis is in units of the standard deviation of the cross-correlation function. A single strong peak is seen in the cross-correlations from 2007 May 9, 2007 August 2, 2008 September 19, and 2008 October 10. The reasonably strong peak on 2007 June 9 is identified as probably arising from imperfect telluric line removal or random noise, since it has $v > v_{\max}$ given by equation 1.

star as template. Figure 5 shows the cross-correlations of the telluric-corrected spectra with a 6100K model for all of the observations. Table 4 summarizes the sensitivity and cross-correlation significance. The detection rate is the fraction of the 17 radial velocities between -400 and 400 km s^{-1} that were correctly detected in the sensitivity analysis (Table 3, step 2). The variation in detection rate is due to the different signal-to-noise levels and telluric line corrections in the observations at different dates. The expected significance is the median significance of the radial velocities which were detected in the sensitivity analysis, in units of the standard deviation of the cross-correlation function. The observed significance

and velocity are for the observed peaks. The velocities in Table 4 are corrected for the barycentric motion and the known systematic radial velocity of HIP 92855, while those in Figure 5 are not.

As Table 4 shows, a 6100K star orbiting HIP 92855 is at the limit of detectability with the direct spectral detection method. With the exception of the observation on 2007 September 16, the cross-correlations for the dates with the highest detection rates have a single large peak. We consider this an excellent candidate for follow-up observations.

If HIP 92855 is a true binary system, evolutionary tracks by Landin et al. (2008) give a secondary star




FIG. 6.— Completeness diagram for the full sample of main-sequence B stars, split up by the effective temperature of the secondary star. The points correspond to the individual stars in the sample, and their sizes reflect the signal-to-noise ratio in the spectrum. Note that the signal-to-noise is calculated after the telluric line removal, and counts any telluric residuals as noise. The figures are also color-coded by the fraction of trials that detected the companion (see section 6). Contours are drawn to guide the eye. The red areas in each plot indicate the regions for which our sample is complete.

mass of $1.2 \pm 0.2 M_{\odot}$. The mass of the primary star is $7.8 \pm 0.2 M_{\odot}$ (Tetzlaff et al. 2010), giving a mass ratio of $q = 0.15 \pm 0.04$. The maximum radial velocity, observed on 2007 August 2, was 234 km s^{-1} . If this is the radial velocity semi-amplitude and if the companion is on a circular orbit, the binary orbit would have a period of 6.8 days. If the true velocity semi-amplitude is larger either because no observation was taken when the companion star was at quadrature or because the orbit is inclined, the period would be shorter than this. If the companion star is on an eccentric orbit, the period could be longer than 6.8 days if the large velocity observed was near periastron.

6. COMPLETENESS

We now estimate the completeness of the direct spectral detection method applied to this data set. For each telluric-corrected observation, we created a series of synthetic binary-star spectra by adding stellar models to the data at various flux ratios, temperatures, and radial velocities. We used evolutionary tracks from Landin et al. (2008) to find the luminosity of model companion stars with temperatures ranging from 3000K to 7000K in steps of 500 K. To find the model flux ratio F_s/F_p , we used the best-fit age for each star quoted in Table 1, as well as the best-fit age $\pm \sigma_{age}$. Model secondary spectra generated with the Phoenix code (Hauschildt et al. 1999) were added to the telluric-corrected observations at 17

different radial velocities ranging from -400 to $+400 \text{ km s}^{-1}$. Changing the radial velocity of the model spectrum changes where the companion spectral lines fall with respect to the telluric lines. Finally, we cross-correlated each synthetic spectrum with its corresponding model secondary star spectrum, and examined the cross correlation function.

If the highest peak in the cross-correlation function was at the correct velocity, the companion was considered detected. We then tabulated how many times the companion star was detected in the 17 radial velocity trials. Figure 6 shows the fraction of trials that detected the companion for all of the model radial velocities, as a function of primary (B-star) mass and the binary mass-ratio. The points correspond to individual spectra, with their sizes indicating the signal-to-noise ratio in the spectrum, and the contours are drawn by interpolating between the points. The four panels are for different companion star temperatures. Companion stars with effective temperatures from 4600 – 5400 K have large regions with a very high detection rate. Stars cooler than about 4600 K are too dim to detect without much higher signal-to-noise ratios than present in our dataset, and stars hotter than about 5400 K do not have a strong CO bandhead and so the cross-correlation function is not as sensitive.

Figure 6 shows that the direct spectral detection method is able to find companion stars with a mass-ratio of $q \approx 0.1 - 0.2$, for a range of effective temperatures.

The regions with a detection rate near 1 are completely sampled, and a companion star in that region would be detected. For primary stars with $M < 10M_{\odot}$, we are sensitive to almost all companions with $4600 < T_{\text{eff}} < 5400$ K.

7. MULTIPLICITY FRACTION

We have not found any unambiguous low mass-ratio companions in our sample, though we do have two candidates that require follow-up observations (HIP 92855 and HIP 26713). From the work described in section 6, we define a range of mass-ratios for which the direct spectral detection method is sensitive for each primary (B-) star. We can then rule out any companions with mass-ratios in that range, for that primary star.

In order to convert these star-by-star limits on the presence of a companion into upper limits on the multiplicity fraction of the parent population, we first count the number of stars that rule out companions in a particular range of mass-ratios. We then apply binomial statistics, where the probability P of finding k companions from n samples of a parent population with a true binary fraction p is given by

$$P(k|p, n) = \frac{n!}{k!(n-k)!} p^k (1-p)^{n-k} \quad (3)$$

For no detected binary companions ($k=0$), the corresponding likelihood function for the binary fraction is

$$P(p|k=0, n) = (n+1) \cdot (1-p)^n \quad (4)$$

A 90% upper limit is given by

$$0.9 = \int_0^p (n+1) \cdot (1-p')^n dp' \quad (5)$$

with solution

$$p_{90} = 1 - 0.1^{\frac{1}{n+1}} \quad (6)$$

A similar derivation gives 90% upper limits for one detection ($k=1$). Figure 7 shows the 90% upper limits to the binary fraction as a function of mass-ratio. To find n in equation 6, we counted the number of stars that ruled out a companion at the given mass-ratio. We only counted companions that were found in all 17 radial velocity trials (see section 6), and were always found with at least 4σ significance. We also included upper limits assuming that HIP 92855, the more likely of our two candidates, is a true binary system. Figure 7 also shows the lower multiplicity limit set by Evans et al. (2011) (blue dotted line) and the *intrinsic* O star mass-ratio distribution derived by Sana et al. (2012). Evans et al. (2011) do not split their multiplicity by mass-ratio, and so the line shown in figure 7 is an average value. While we include them for comparison with our results, neither of these studies are directly comparable to our sample. Sana et al. (2012) have only O stars in their sample and are only able to measure mass-ratios $q \approx 0.2-1$, although they consider mass-ratios down to $q = 0.1$ when deriving the intrinsic distribution. Evans et al. (2011) are sensitive to similar mass-ratios as our sample, but they sample late B-stars (B4-B9) while we sample early B stars (B0-B5). Our results are almost perfectly complementary to

those of Evans et al. (2011). It is encouraging that our upper limits for $0.1 < q < 0.2$, where our sample is most complete, lie in between the results of Sana et al. (2012) who measure the binary fraction of more massive primaries, and Evans et al. (2011) who measure the binary fraction of less massive primaries than we do.

The above analysis assumes that the sample of B-stars given in Table 1 is representative of the B-star population as a whole. Most of the sample stars are field B-stars, which have a lower overall multiplicity than cluster or association B-stars (Mason et al. 2009). However, the close binaries this method is sensitive to would be difficult to disrupt with dynamical interactions in a cluster environment, and we therefore expect this sample to be representative of both populations. A potential complication is that telluric standard stars are often chosen specifically because they are *not* known binary systems. While this may introduce a bias for large mass-ratios, the direct spectral detection method is sensitive to low mass-ratio companions that may not have been found with other methods such as classical spectroscopy or imaging and so companions with $q \lesssim 0.2$ may be less effected. The amount of bias introduced into the above measurement depends on how carefully the individual observers chose the telluric standard stars, and so is very difficult to assess.

8. CONCLUSION

We have described a new technique for finding binary systems with a flux ratio of $F_p/F_s \approx 100$, where F_p and F_s are the fluxes from the primary and secondary star, respectively. In this technique, which we call the direct spectral detection technique, we use high signal-to-noise, high resolution spectra of a binary candidate. We remove the contamination from the Earth's atmosphere with the telluric modeling code LBLRTM, and cross-correlate the residuals with a library of stellar models for late type stars (F2-M5). A binary detection would appear as a strong peak in the cross-correlation function.

We prove the feasibility of the direct spectral detection method by adding a synthetic signal to real data, and successfully recovering it. We further investigate the completeness of the method in section 6. This method is sensitive to detecting a range of companion stars, set by the spectral type and age of the primary and the signal-to-noise ratio of the observation. Our sample is sensitive to almost all companion stars with $4600 < T < 5400$, corresponding to binary mass-ratios of $0.1 \lesssim q \lesssim 0.2$.

We have applied this technique to a sample of 34 archived main sequence early B-stars (B0-B5) with spectra taken with the CRILES near-infrared spectrograph. We found no unambiguous companions in our sample, but identify two targets as candidate binary systems: HIP 92855 and HIP 26713. HIP 92855 is B2.5V type star, with a candidate companion star with effective temperature $T = 6100$ K and mass $1.2 \pm 0.2M_{\odot}$. Such a companion star is very near the detection limit of the direct spectral detection technique and deserves further follow-up observations. HIP 26713 is a B1.5V type star, with a candidate companion star with $T = 5600$ K and $M = 1.6 \pm 0.2M_{\odot}$. This star was only observed once in our sample, and so may be a series of incompletely removed telluric absorption lines masquerading as a companion star.




FIG. 7.— Estimates of the binary fraction of B0-B5 stars, as a function of binary mass-ratio. This work found no unambiguous companions, and so we give 90% upper limits (solid black line). 90% upper limits are also given assuming that HIP 92855 is a real binary system (dotted black line). The upper limits are only different within the 1σ error bars on the mass-ratio for HIP 92855. The nearly flat distribution found by Sana et al. (2012) is shown as the dashed red line. The average binary fraction found by Evans et al. (2011) is also shown (dash-dot blue line). The Evans et al. (2011) value is a *lower* limit and an average over all mass-ratios from $0.1 < q < 0.3$, but they estimate that their sample is very complete, and so the true multiplicity fraction is quite close to their value.

We set upper limits on the binary fraction of early B stars as a function of binary mass-ratio (see Figure 7). As well as showing the upper limit for no detections in our sample, we also show the binary fraction upper limit assuming the HIP 92855 is a true binary system. Our upper limits are strongest for mass-ratios $q \approx 0.1-0.15$, and are about 20%. We compare our limits to the intrinsic binary mass-ratio distribution for O-type primaries derived by Sana et al. (2012), as well as the lower limit *average* binary fraction seen by Evans et al. (2011) for late B-stars (B4-B9). Our strongest upper limits ($0.1 \leq q \leq 0.15$) fall in between these two previous studies.

Companion stars formed by circumstellar disk instability are expected to have typical mass-ratios near $q = 0.1$ (Kratter & Matzner 2006; Stamatellos & Whitworth 2011), near where our upper limits are strongest. If there was a large population of low mass-ratio companions formed by disk fragmentation, we would expect to see a peak in the mass-ratio distribution near $q \approx 0.1$. Since our results agree well with the nearly flat mass-ratio distribution derived by Sana et al. (2012), it is unlikely that such a peak exists. There are several possible interpretations of this result, three of which we give below.

1. Stellar companions formed by disk instability have a much lower characteristic mass-ratio than $q = 0.1$ which remain invisible to observations.
2. The mass-ratio distribution of companions formed by disk instability is very broad, and so we would

not expect a strong peak in the observed mass-ratio distribution. This interpretation may be supported by the flatness of the mass-ratio distribution as well as disk instability simulations that end with massive companions (e.g. Krumholz et al. 2009; Clarke 2009).

3. Disk instability is not a dominant formation mechanism for low mass-ratio binary systems, and molecular core fragmentation alone can generate the nearly flat mass-ratio distribution down to low mass-ratios.

It is difficult to distinguish between these interpretations at this time. More observational work, as well as computational work, is required to explain the binary properties of high-mass stars.

We would like to acknowledge Andreas Seifahrt, Rob Robinson, and Daniel Jaffe for their generous help with the telluric modeling procedure and some of the statistical aspects of this work. We would also like to thank the referee for a quick review and many helpful comments. This research has made use of the following online resources: the SIMBAD database and the VizieR catalogue access tool at CDS, Strasbourg, France, and the ESO Science Archive Facility. Funding for this work was provided by a National Science Foundation CAREER award to Sarah Dodson-Robinson (AST-1055910) and by start-up funding from the University of Texas College of Natural Sciences.

TABLE 1 Full star sample

Star	Spectral Type	Age (Myr)	Distance (pc)	Maximum Separation (AU)	Number of Observations
HIP 23364	B3V	31.6 ± 0.6	31.65	25.32	1
HIP 26713	B1.5V	7.2 ± 2.5	138.89	111.11	1
HIP 27204	B1IV/V	12.6 ± 4.6	408.2	326.5	1
HIP 30122	B2.5V	32 ± 0.4	111.1	88.9	4
HIP 32292	B2V	8.2 ± 0.1	1111.1	888.9	1
HIP 39866	B3V	25.1 ± 2.6	840.3	672.3	1
HIP 48782	B3V	32.3 ± 0.6	370.4	296.3	1
HIP 52370	B3V	17.2 ± 1.3	58.14	46.51	2
HIP 52419	B0Vp	4 ± 0.7	250	200	2

TABLE 1 – Continued

Star	Spectral Type	Age (Myr)	Distance (pc)	Maximum Separation (AU)	Number of Observations
HIP 54327	B2V	11.7 ± 6.2	252.5	202.0	3
HIP 55667	B2IV-V	22.5 ± 2.6	847.5	678.0	1
HIP 60823	B3V	25.3 ± 6.3	39.53	31.62	5
HIP 62327	B3V	8.2 ± 1.8	121.95	97.56	4
HIP 63945	B5V	27.3 ± 11.4	36.63	29.3	1
HIP 61585	B2IV-V	18.3 ± 3.2	96.7	77.4	8
HIP 62327	B3V	8.2 ± 1.8	117.9	94.3	4
HIP 63007	B4Vne	53.3 ± 8.1	117.6	94.1	2
HIP 63945	B5V	27.3 ± 11.4	119.6	95.7	1
HIP 67796	B2V	15.4 ± 0.4	970.9	776.7	1
HIP 68282	B2IV-V	13 ± 2	76.92	61.54	2
HIP 68862	B2V	9.1 ± 3.8	109.89	87.91	1
HIP 71352	B1Vn + A	5.6 ± 1	178.57	142.86	2
HIP 73129	B4Vnpe	27.1 ± 6.1	36.9	29.52	1
HIP 74110	B3V	33.2 ± 7.3	30.12	24.1	1
HIP 76126	B3V	15.9 ± 1.3	62.89	50.31	1
HIP 78820	B0.5V	13.8 ± 0.4	123.9	99.1	1
HIP 80582	B4V	50.1 ± 14	19.96	15.97	2
HIP 80815	B3V	10.5 ± 2.1	95.24	76.19	4
HIP 81266	B0.2V	5.7 ± 1	175.44	140.35	12
HIP 82514	B1.5Vp+	20 ± 2	50	40	1
HIP 87314	B2/B3Vnn	23.2 ± 2.9	43.1	34.48	7
HIP 92855	B2.5V	31.4 ± 0.4	31.85	25.48	7
HIP 92989	B3V	7.9 ± 2.1	126.58	101.27	1
HIP 97611	B5V	45 ± 10	66.67	53.33	1

TABLE 2 Summary of adjusted line strengths. The units of line strength are $\text{cm}^{-1}/(\text{molecule} \times \text{cm}^{-2})$

Wavelength (nm)	Molecule	Old Strength	New Strength
2317.12	CH ₄	5.445×10^{-21}	5.034×10^{-21}
2318.24	H ₂ O	1.400×10^{-24}	2.256×10^{-24}
2328.51	CH ₄	2.521×10^{-21}	2.371×10^{-21}
2328.56	CH ₄	1.270×10^{-21}	1.358×10^{-21}
2340.12	CH ₄	3.085×10^{-21}	2.963×10^{-21}
2340.36	CH ₄	3.343×10^{-21}	3.211×10^{-21}
2351.64	H ₂ O	1.670×10^{-23}	1.393×10^{-23}
2351.69	H ₂ O	1.085×10^{-23}	7.985×10^{-24}
2352.43	CH ₄	3.144×10^{-23}	4.031×10^{-24}
2352.45	H ₂ O	4.639×10^{-23}	4.939×10^{-23}
2353.62	CH ₄	2.708×10^{-21}	2.654×10^{-21}
2355.82	CH ₄	5.101×10^{-21}	4.949×10^{-21}
2358.9	CH ₄	5.160×10^{-21}	4.710×10^{-21}
2364.03	H ₂ O	1.408×10^{-23}	1.217×10^{-23}
2367.23	H ₂ O	2.078×10^{-23}	2.182×10^{-23}
2370.35	CH ₄	4.028×10^{-21}	3.625×10^{-21}
2370.41	CH ₄	2.437×10^{-21}	2.021×10^{-21}
2370.75	CH ₄	1.466×10^{-21}	9.138×10^{-22}
2371.39	H ₂ O	3.905×10^{-23}	3.171×10^{-23}
236.62	H ₂ O	1.146×10^{-23}	9.186×10^{-24}
2376.63	H ₂ O	3.824×10^{-24}	3.820×10^{-24}
2378.2	H ₂ O	1.134×10^{-22}	1.021×10^{-22}
2379.67	H ₂ O	6.334×10^{-24}	8.408×10^{-24}
2385.98	H ₂ O	6.051×10^{-23}	5.407×10^{-23}

TABLE 3 Summary of Cross-Correlation Function Peak Rejection Steps.
See Section 5 for more information

Step	Description	Method
1	Telluric Residual Peak Identification	Compare cross-correlation function of telluric-corrected spectrum with that of an uncorrected spectrum.
2	Sensitivity Analysis	Check that signal-to-noise ratio is high enough to detect secondary candidate at a range of velocities
3	Velocity Analysis	Check that a blackbody with the candidate temperature can exist as close to the primary B-star as the velocity indicates (assumes circular orbit)

TABLE 4 Summary of HIP 92855 observations. Significance is in units of the standard deviation of the cross-correlation function. The detection rate and expected significances are from the sensitivity analysis (Table 3, step 2).

Date	Detection Rate	Expected Significance	Observed Significance	Velocity (km s ⁻¹)
2007 May 9	0.35	3.3 σ	4.1 σ	-74
2007 June 9	0.18	3.6 σ	N/A	N/A
2007 July 25	0.35	3.7 σ	N/A	N/A
2007 August 2	0.47	3.6 σ	3.5 σ	-234
2007 September 16	0.82	4.2 σ	N/A	N/A
2008 September 19	0.71	3.4 σ	4.1 σ	-126
2008 September 10	0.59	3.3 σ	4.0 σ	116

REFERENCES

- Bate, M. R. 2000, *MNRAS*, 314, 33
—, 2012, *MNRAS*, 419, 3115
Bate, M. R., Bonnell, I. A., & Bromm, V. 2002, *MNRAS*, 336, 705
Bate, M. R., Bonnell, I. A., & Price, N. M. 1995, *MNRAS*, 277, 362
Bonnell, I. A. & Bate, M. R. 2005, *MNRAS*, 362, 915
Boss, A. P. 1986, *ApJS*, 62, 519
—, 2006, *ApJ*, 643, 501
—, 2011, *ApJ*, 731, 74
Boss, A. P. & Bodenheimer, P. 1979, *ApJ*, 234, 289
Carroll, B. W. & Ostlie, D. A. 2006, An introduction to modern astrophysics and cosmology, ed. Carroll, B. W. & Ostlie, D. A.
Chacón, A., Cuevas, O., Pozo, D., Marín, J., Oyanadel, A., Dougnac, C., Cortes, L., Illanes, L., Caneo, M., Curé, M., Sarazin, M., Kerber, F., Smette, A., Rabanus, D., Querel, R., & Tompkins, G. 2010, in *Society of Photo-Optical Instrumentation Engineers (SPIE) Conference Series*, Vol. 7733, *Society of Photo-Optical Instrumentation Engineers (SPIE) Conference Series*
Clarke, C. J. 2009, *MNRAS*, 396, 1066
Clough, S., Shephard, M., Mlawer, E., Delamere, J., Iacono, M., Cady-Pereira, K., Boukabara, S., & Brown, P. 2005, *Journal of Quantitative Spectroscopy and Radiative Transfer*, 91, 233
 $U - R$ linklabel
Dodson-Robinson, S. E., Veras, D., Ford, E. B., & Beichman, C. A. 2009, *ApJ*, 707, 79
Evans, C. J., Bastian, N., Beletsky, Y., Brott, I., Cantiello, M., Clark, J. S., Crowther, P. A., de Koter, A., de Mink, S. E., Dufton, P. L., Dunstall, P., Gieles, M., Gräfener, G., Hénault-Brunet, V., Herrero, A., Howarth, I. D., Langer, N., Lennon, D. J., Maíz Apellániz, J., Markova, N., Najarro, F., Puls, J., Sana, H., Simón-Díaz, S., Smartt, S. J., Stroud, V. E., Taylor, W. D., Trundle, C., van Loon, J. T., Vink, J. S., & Walborn, N. R. 2010, in *IAU Symposium*, Vol. 266, *IAU Symposium*, ed. R. de Grijs & J. R. D. Lépine, 35–40
Evans, N. R., DeGioia-Eastwood, K., Gagné, M., Townsley, L., Broos, P., Wolk, S., Nazé, Y., Corcoran, M., Oskinova, L., Moffat, A. F. J., Wang, J., & Walborn, N. R. 2011, *ApJS*, 194, 13
Gagné, M., Caillault, J.-P., Stauffer, J. R., & Linsky, J. L. 1997, *ApJ*, 478, L87
Hauschildt, P. H., Allard, F., & Baron, E. 1999, *ApJ*, 512, 377
Huélamo, N., Neuhauser, R., Stelzer, B., & Zinnecker, H. 2000, *Ap&SS*, 272, 311
Kerber, F., Querel, R., Hanuschik, R., Chacón, A., Sarazin, M., & Project Team. 2010, *The Messenger*, 141, 9
Klahr, H. & Brandner, W. 2006, *Planet Formation*, ed. Klahr, H. & Brandner, W.
Kratter, K. M. & Matzner, C. D. 2006, *MNRAS*, 373, 1563
Kratter, K. M., Matzner, C. D., & Krumholz, M. R. 2008, *ApJ*, 681, 375
Kroupa, P., Bouvier, J., Duchêne, G., & Moraux, E. 2003, *MNRAS*, 346, 354
Krumholz, M. R., Klein, R. I., & McKee, C. F. 2007, *ApJ*, 656, 959
—, 2012, *ApJ*, 754, 71
Krumholz, M. R., Klein, R. I., McKee, C. F., Offner, S. S. R., & Cunningham, A. J. 2009, *Science*, 323, 754
Landin, N. R., Mendes, L. T. S., & Vaz, L. P. R. 2008, *VizieR Online Data Catalog*, 349, 40209
Lebovitz, N. R. 1974, *ApJ*, 190, 121
—, 1984, *ApJ*, 284, 364
Lyttleton, R. A. 1953, *The stability of rotating liquid masses : [bibliog.]* (Univ. Press, Camb. :)
Maíz Apellániz, J. 2010, *A&A*, 518, A1
Mason, B. D., Hartkopf, W. I., Gies, D. R., Henry, T. J., & Helsel, J. W. 2009, *AJ*, 137, 3358
Porter, J. M. & Rivinius, T. 2003, *PASP*, 115, 1153
Rothman, L., Gordon, I., Barbe, A., Benner, D., Bernath, P., Birk, M., Boudon, V., Brown, L., Campargue, A., Champion, J.-P., Chance, K., Coudert, L., Dana, V., Devi, V., Fally, S., Flaud, J.-M., Gamache, R., Goldman, A., Jacquemart, D., Kleiner, I., Lacome, N., Lafferty, W., Mandin, J.-Y., Massie, S., Mikhailenko, S., Miller, C., Moazzen-Ahmadi, N., Naumenko, O., Nikitin, A., Orphal, J., Perevalov, V., Perrin, A., Predoi-Cross, A., Rinsland, C., Rotger, M., imekov, M., Smith, M., Sung, K., Tashkun, S., Tennyson, J., Toth, R., Vandaele, A., & Auwera, J. V. 2009, *Journal of Quantitative Spectroscopy and Radiative Transfer*, 110, 533 ,
jce:title;HITRANj/ce:title; $U - R$ linklabel
Sana, H., de Mink, S. E., de Koter, A., Langer, N., Evans, C. J., Gieles, M., Gosset, E., Izzard, R. G., Le Bouquin, J.-B., & Schneider, F. R. N. 2012, *Science*, 337, 444
Sana, H. & Evans, C. J. 2011, in *IAU Symposium*, Vol. 272, *IAU Symposium*, ed. C. Neiner, G. Wade, G. Meynet, & G. Peters, 474–485
Sana, H., Gosset, E., & Evans, C. J. 2009, *MNRAS*, 400, 1479
Schmitt, J. H. M. M. 1997, *A&A*, 318, 215
Seifahrt, A., Käufel, H. U., Zängl, G., Bean, J. L., Richter, M. J., & Siebenmorgen, R. 2010, *A&A*, 524, A11
Stamatellos, D. & Whitworth, A. 2011, *Research, Science and Technology of Brown Dwarfs and Exoplanets: Proceedings of an International Conference held in Shanghai on Occasion of a Total Eclipse of the Sun, Shanghai, China*, Edited by E.L. Martin; J. Ge; W. Lin; EPJ Web of Conferences, Volume 16, id.05001, 16, 5001
Tetzlaff, N., Neuhaeuser, R., & Hohle, M. M. 2010, *VizieR Online Data Catalog*, 741, 190
Tohline, J. E. 2002, *ARA&A*, 40, 349
Tohline, J. E. & Durisen, R. H. in , *IAU Symposium*, Vol. 200, *The Formation of Binary Stars*, ed. H. ZinneckerR. Mathieu, 40
Westin, T. N. G. 1985, *A&AS*, 60, 99
Zinnecker, H. & Yorke, H. W. 2007, *ARA&A*, 45, 481